

**Kiwa GmbH**  
Bautest Augsburg  
Finkenweg 7  
86368 Gersthofen

Kiwa GmbH, Finkenweg 7, 86368 Gersthofen

Hauff-Technik GmbH & Co. KG  
Robert-Bosch-Straße 9  
89428 Hermaringen

T: +49 (0) 821 72024 - 0  
F: +49 (0) 821 72024 - 40  
E: [Infokiwaaugsburg@kiwa.de](mailto:Infokiwaaugsburg@kiwa.de)

[www.kiwa.de](http://www.kiwa.de)

**Project / Plant:** Water tightness test of the single wall insert Hauff HSI150-K/150 and system cover Hauff HSI150-DT, embedded in a standard concrete test block with reinforcement (system according to Lithobeton)

**Order date:** 5 March 2019

**Product description:** Single wall insert Hauff HSI 150-K/150  
System cover Hauff HSI150-DT

**Order:** Water tightness test with  $\geq 2,5$  bar for 28 days,  $\geq 3,5$  bar for 7 days and  $\geq 4,0$  bar for 7 days of the single wall insert Hauff HSI 150-K/150 and system cover Hauff HSI150-DT

**Number of samples / tests:** 3 tests

**Sampling:** on: - / by: Applicant

**Date of delivery:** 5 March 2019

**Testing period:** 5 March - 25 April 2019

**Contact:** B. Eng. David Röck  
Tel. +49 821 72024-14

**Remark:** Translation of Test Report A1942021-02  
25 April 2019

Gersthofen, 25 April 2019  
rö/bö

p. p.



B. Eng. David Röck  
- Project manager -



p. p.



Jörg Bölzle  
- Project manager -

The test results relate only on the items tested. Without the written approval of the testing laboratory, a duplication of the test report is not permitted.

Geschäftsführer: Prof. Dr. Roland Hüttl  
Amtsgericht Hamburg, HRB 130568, St.Nr.: 46/736/03268



## CONTENTS

	Page
<b>1. General</b> .....	<b>3</b>
<b>2. References</b> .....	<b>3</b>
<b>3. Test procedure</b> .....	<b>3</b>
3.1 Test preparation (Hauff-Technik GmbH & Co. KG) .....	3
3.2 Water tightness test (Kiwa GmbH, Bautest Augsburg).....	4
<b>4. Test results</b> .....	<b>6</b>
<b>5. Summary</b> .....	<b>6</b>
<b>6. Calibration certificates</b> .....	<b>7</b>

## 1. General

Kiwa GmbH, Bautest Augsburg, was contracted by Hauff-Technik GmbH & Co. KG to test the water tightness of the single wall insert Hauff HSI150-K/150 and system cover Hauff HSI150-DT embedded in a standard concrete test block with reinforcement made by the manufacturer Lithobeton nv.

Therefore an assembled test setup with concrete embedded single wall insert Hauff HSI150-K/150 and system cover Hauff HSI150-DT was delivered by Hauff-Technik GmbH & Co. KG to our test laboratory in Augsburg, Germany (see Figure 1).



Figure 1. Delivered test setups.

## 2. References

- [1] Hauff-Technik GmbH & Co. KG - „Montageanweisung HSI 90/HSI 150“, ma\_HSI 90\_150 so\_wird\_einbetoniert\_151202“.
- [2] WIKA Polska sp. z o.o. sp. k. - “Inspection certificate according to EN 10204 - 3.1, Certification No. WC006945. 19 March 2019.
- [3] WIKA Polska sp. z o.o. sp. k. - “Inspection certificate according to EN 10204 - 3.1, Certification No. WC006962. 20 March 2018.

## 3. Test procedure

### 3.1 Test preparation (Hauff-Technik GmbH & Co. KG)

The installation of the test setup was performed by Hauff-Technik GmbH & Co. KG, the manufacturer of the single wall insert and of the system cover.

According to information given by the manufacturer the test setup was assembled as follows:

The test block (500 x 500 x 200 mm) made by Lithobeton nv with the embedded single wall insert Hauff HSI150-K/150 was delivered to Hauff-Technik GmbH & Co. KG (see an example in Figure 2).

After a visual inspection of the concrete quality Hauff-Technik GmbH & Co. KG installed the system cover Hauff HSI150-DT into the opening of the single wall insert at the pressure side of the test block (see Figure 3).

The testing area was covered with a stainless steel cover plate with pressure reducer and calibrated manometers (see Chapter 6). The sealing of the cover plate was performed with the help of an EPDM plate and clamping pressure.



Figure 2. Examples for a test block with embedded single wall insert Hauff HSI150-K/150.



Figure 3. Test block with concrete embedded single wall insert Hauff HSI150-K/150 and system cover Hauff HSI150-DT.

### 3.2 Water tightness test (Kiwa GmbH, Bautest Augsburg)

The test setup assembled by Hauff-Technik GmbH & Co. KG was built up in accordance to Section 3.1 with one manometer (see Figure 4 to Figure 6).

Calibration certificates of the used manometers can be seen at Chapter 6. An additional calibration of the manometers which were delivered by Hauff-Technik GmbH & Co. KG did not take place at Kiwa GmbH.

After prior consultation with the manufacturer the tests of the water tightness were performed with  $\geq 2,5$  bar for 28 days,  $\geq 3,5$  bar for 7 days and  $\geq 4,0$  bar for 7 days. The test with  $\geq 2,5$  bar and  $\geq 3,5$  bar was performed with permanently attached water pressure. The test with  $\geq 4,0$  bar was performed with a water/air mixture.




Figure 4. Detail of the test setup - manufacturer's drawing.




Figure 5. Detail of the single wall insert Hauff HSI150-K/150 - manufacturer's drawing.




Figure 6. Detail of the system cover Hauff HSI150-DT - manufacturer's drawing.

#### 4. Test results

During the water tightness tests no leakages were detected (see Table 1).

Table 1. Results of the water tightness tests.

Test specimen	Water pressure at the beginning of testing [bar]	Water pressure at the end of testing [bar]	Testing period [d]	Remark
HSI15-DT	≥ 2,5	≥ 2,5	28	No leakages were detected
	≥ 3,5	≥ 3,5	7	
	≥ 4,0	≥ 4,0	7	

#### 5. Summary

*During the water tightness tests of the single wall insert Hauff HSI150-K/150 and the system cover Hauff HSI150-DT, embedded in a reinforced standard concrete test block by made by Lithobeton nv, no leakages were detected at ≥ 2,5 bar for 28 days, ≥ 3,5 bar for 7 days and ≥ 4,0 bar for 7 days.*

## 6. Calibration certificates

440H

Wika Polska sp. z o.o. sp. k.

Inspection certificate according to EN 10204 - 3 1  
Abnahmeprüfzeugnis nach EN 10204 - 3 1



Customer: Kunde		Haufl. Technik GmbH & Co. KG Robert-Bosch-Str. 9 Herrmaringen 89168 DE	Page Seite	1 / 2
			Certificate No. Zeugnis-Nr.	WC006845
			Date Datum	19.03.2018
Customer Order No Kundenbestellnummer	175211375	Customer Part No Kunden Artikel-Nr.	Order Date Bestelldatum	
Order No / Item Auftrags-Nr. / Pos.	22606960/2 32210713	Part No. Artikel-Nr.	14225186	
Model Typ	111.1D.063	Serial number Seriennummer	5400TD61	Scale range Anzeigebereich
Class Klasse	2.50 %	Tag No Messstellen-Nr.		0 ... 2.5 bar rel.
Reference Referenzgerät	CPG2500 0.01% ±1 ... 2.7 bar rel.	Calibration No. Kalibrierungsnummer	SW-102-1-17 WPL 17-04	
Article text Artikeltext	Bourdon tube pressure gauges, model 111			

Wika Polska sp. z o.o. sp. k.

Inspection certificate according to EN 10204 - 3.1  
Abnahmeprüfzeugnis nach EN 10204 - 3.1



Page 2 / 2  
Seite


Customer: Hauff-Technik GmbH & Co. KG  
Kunde: Robert-Bosch-Straße 9  
Herrnaringen 89568 DE

Certificate No: WC006945  
Zeugnis-Nr.

Date: 19.03.2018  
Datum

Result: Temperature 20°C +/- 5 K  
Ergebnis: Temperatur

Test Item Prüfung bar	Standard Referenz bar	Measured Werte bar	rel. Deviation rel. Abweichung bar	Deviation Abweichung %	Hysteresis Hysterese %
0.500	0.522	0.496	0.509	-0.009	-0.37
1.000	1.014	1.010	1.012	-0.012	-0.48
1.500	1.509	1.491	1.500	0.000	0.00
2.000	2.016	2.004	2.010	-0.010	-0.40
2.500	2.512	2.512	2.512	-0.012	-0.49



Object keeps the specification.  
Der Kalibriergegenstand hält die Fehlergrenzen nach Herstellerangaben ein.

Calibration was carried out according to the following norm: DIN EN 837-1  
Die Kalibrierung erfolgte auf der Grundlage der folgenden Norm:

Remarks / Bemerkung:

Inspection Representative: DAN  
Abnahmebeauftragter: Daniel Kotkowski  
Examiner: S. Pekarski  
Prüfer

This document was created automatically and needs no signature.  
Dieses Dokument wurde automatisch erstellt und gilt ohne Unterschrift.

45811

**Wika Polska sp. z o.o. sp. k.**

Inspection certificate according to EN 10204 - 3.1  
Abnahmeprüfzeugnis nach EN 10204 - 3.1



Page  
Seite 1 / 2

Customer  
Kunde: **Mauff-Technik GmbH & Co KG**  
**Robert-Bosch-Straße 9**  
**Herrmaringen**  
**89568**  
**DE**

Certificate No  
Zeugnis-Nr **WC008882**

Date  
Datum **2018-03-20**

Customer Order No Kundenbestellnummer	<b>175211375</b>	Customer Part No Kunden Artikel-Nr	Order Date Bestelldatum	
Order No. / Item Auftrags-Nr. / Pos	<b>2298880/3</b> <b>32210715</b>	Part No. Artikel-Nr	<b>14225187</b>	
Model Typ	<b>111.10.083</b>	Serial number Seriennummer	<b>8400TD8D</b>	Scale range Anzeigebereich <b>0 .. 6 bar rel</b>
Class Klasse	<b>2.50 %</b>	Tag No Messstellen-Nr		
Reference Referenzgerät	<b>CPG2800 0,01% IS-60 -1 .. 32,1 bar rel.</b>	Calibration No. Kalibriernummer	<b>SW-101-1-17 WPL 17-04</b>	
Article text Artikeltext	<b>Bourdon tube pressure gauges,model 111</b>			

Wika Polska sp. z o.o. sp. k.

Inspection certificate according to EN 10204 - 3.1  
Abnahmeprüfzeugnis nach EN 10204 - 3.1



Page 2 / 2

Seite

Customer: Hauff-Technik GmbH & Co. KG  
Kunde: Robert-Bosch-Straße 9  
Herrlingen 89568  
DE


Certificate No. WC006962  
Zeugnis-Nr.

Date: 2018-03-20  
Datum

Result  
Ergebnis

Temperature: 20°C +/- 5 K  
Temperatur

Test Item Prüfung bar	Standard Referenz bar	Measured Messwert bar	rel. Deviation rel. Abweichung bar	Deviation Abweichung %	Hysteresis Hysterese %
1,000	0,952	0,944	0,948	0,052	-0,14
2,000	1,952	1,967	1,960	0,040	0,25
3,000	2,953	2,925	2,940	0,060	-0,44
4,000	3,962	3,965	3,963	0,037	0,05
5,000	5,988	5,988	5,988	0,012	0,00



Object keeps the specification  
Der Kalibriergegenstand hält die Fehlergrenzen nach Herstellerangaben ein.

Calibration was carried out according to the following norm: DIN EN 837-1  
Die Kalibrierung erfolgte auf der Grundlage der folgenden Norm:

Remarks / Bemerkung:

Inspection Representative (N.D.): Daniel Kotlowski  
Abnahmebeauftragter: Daniel Kotlowski  
Examiner (Prüfer): J. Glodowski

This document was created automatically and needs no signature.  
Dieses Dokument wurde automatisch erstellt und gilt ohne Unterschrift.